



NOTICE INVITING TENDER
CMP DEGREE COLLEGE, ALLAHABAD
UNIVERSITY OF ALLAHABAD-211002

TENDER NOTICE NO: CMP/407/2022

DATE: 13.06.2022

Sealed Item rate tenders are invited from registered firms up to 2:00 P.M. on 28.06.2022 and shall be opened at 3.00 P.M. on the same day for repair & renovation work at the Law Faculty.


Estimated Cost	EMD	Time of completion	Tender Cost
Rs 21.57 Lakh.	Rs. 44000/-	120 days	Rs. 2000.00/-


Interested parties may download the tender documents from the college web-site address: www.cmpcollege.ac.in and submit the tender document either with the Cash Receipt from Account Section or Demand Draft of the tender cost in favour of **Principal, CMP Degree college, Allahabad** along with the other requirement as stated in the detailed conditions while submitting the tender, write tender No. **CMP/407/2022** on envelope. Date of availability of tender document on College web site from **14.06.2022**

	Date	Time	Venue
Last date of submission of Tender	28.06.2022	2:00pm	Office of the Principal, CMP Degree College
Opening of Tender	28.06.2022	3:00pm	Office of the Principal, CMP Degree College

In the event of any date indicated above is declared as holiday, the next working day of the college shall be considered as the due date for receiving & opening of tenders. Late/delayed offer will not be accepted.

The College administration reserves the right to accept or reject any or all the Tender/s without assigning any reason and to split up work or items of work to divide or distribute the whole work among more than one contractor. The contractors will have no option to refuse such splitting/rejection.


Convener
Building Committee


Principal



**Chaudhary Mahadeo Prasad Degree College, Allahabad
(University of Allahabad)**

TENDER NOTICE NO: CMP/407/2022

DATE: 13/06/2022

To,

M/s

.....

.....

Name of Work: For repair & renovation work at the Law Faculty.


Dear Sir,


Please quote your rates as per attached bill of quantity. Your tender should reach to the office of the undersigned latest by 28.06.2022 up to 2:00 P.M. tender will be opened on 28.06.2022 at 3:00 P.M. on the same date in the presence of desirous bidders.

Terms and Conditions:

- 1 Unsealed & conditional tenders shall not be accepted.
- 2 Bidders have to submit Proof of PAN, GST Certificate.
- 3 Bidders are required to deposit either a cash receipt from Account Section or Demand Draft of Rs. 2000.00 as the cost of tender from in favour of Principal, C.M.P. Degree College,
- 4 Bidders are required to deposit 2% of estimated cost of the work as Earnest Money in form of Demand draft in favour of **Principal, C.M.P. Degree College, Prayagraj.**
- 5 10% Security Deposit will be deposited from the final bill and will be released after period of 12 months.
- 6 College reserves right to reject or accept any or all the tender without assigning any reason thereof or to distribute the whole work between two or more contractor/firms.
- 7 Rates shall be valid for 90 days from the date of opening of tenders.
- 8 Taxes shall be deducted as per rules.
- 9 Applicable GST will be paid to contractors.
- 10 The payment of wages/ allowance and other benefits admissible to persons employed by the contractor for the job shall be the sole responsibility of the contractor as their employer under law.
- 11 The contractor shall be legally liable and responsible for any contravention of any legal requirement and consequent liability with regard to persons deployed by him in connection with the work assigned to him by the College.
- 12 All the litigations will be subjected to the jurisdiction of courts at Allahabad.
- 13 In case the work is not completed in stipulated time penalty of 5% of the value of work will be deducted from the contractors bill subject to maximum of 10% of total amount of bill.
- 14 Standard deductions as per rule will be made from the bill.
- 15 Works executed will be verified by the Architect/College Engineer before releasing payments to the contractor.
- 16 If the work exceeds from the prescribed work then the Contractor has to do the work on the same rate as he has quoted in the tender.

Signature of Contractor
with seal


Convenor, Building Committee


Principal

Chaudhary Mahadeo Prasad Degree College, Allahabad
(University of Allahabad)

TENDER NOTICE NO: CMP/407 /2022

DATE: 13/06/2022

To,

M/s

.....

.....

Dear Sir,

Please quote your rates in attach bill of quantity, sealed tender should reach on or before 28.06.2022 up to 2:00 P.M. in the office of the Principal, C.M.P. Degree College, Allahabad.

Name of Work: For repair & renovation work at the Law Faculty.

S.No.	Item	Qty	Rate	Amount
As per list attached				

Signature of Contractor
with seal

A. Yumar
Convenor, Building Committee

U. Chandra
Principal

Project
Plot
Owners

: Proposed Repair & Renovation Law College
: CMP Degree College Campus, Prayagraj
: Principal, CMP Degree College

SN	Description of Item	No s	L (m)	B (m)	H/D (m)	Qty	Unit	Rate/ Unit	Amt (Rs. Lakhs) incl. GST
	A. Ground Floor								
	GST Multiplying factor as provided for by CPWD in their Rate Analysis								
	Dismantling of RCC Roof Slab & Beams								
	Dismantling RCC Structural Items								
	<i>17.04 Ch 17 694 (17.3) : Dismantling reinforced cement concrete or reinforced brick work</i> including stacking of dismantled materials as directed by Engineer-In-Charge within a distance of 60 meters (200 feet).								
	Front Verandah	1	16.100	4.200	0.150	10.143	Cum		
	Library	1	16.000	4.200	0.150	10.080	Cum		
	Office Verandah	1	12.700	4.000	0.150	7.620	Cum		
	Office	1	6.000	3.500	0.150	3.150	Cum		
	Beam	4	3.500	0.350	0.450	2.205	Cum		
		1	16.100	0.350	0.450	2.536	Cum		
						35.734	Cum		
	Dismantling Existing Plaster Work								
	<i>17.13 Ch 17 706 (17.10) : Dismantling existing plaster</i> including disposal of refuse as directed by Engineer-In-Charge within a distance of 60 meters (200 feet)								
	Wall Plaster:								
	Class Room	6	42.400		4.200	1068.480	Sqm		
	Room Outer	1	100.000		4.200	420.000	Sqm		
	Moot Court Wall	4	37.500		4.200	630.000	Sqm		
		4	3.500		4.200	58.800	Sqm		
	Passage (Outer Wall)	2	23.000		4.200	193.200	Sqm		
	Com Toilet	2	2.300		3.680	16.928	Sqm		
		2	2.270		3.680	16.707	Sqm		
	Staff Toilet	2	3.800		3.680	27.968	Sqm		
		2	3.000		3.680	22.080	Sqm		
	Office	2	5.800		3.680	42.688	Sqm		
		2	9.000		3.680	66.240	Sqm		
	Office Verandah	2	13.000		3.680	95.680	Sqm		
		2	3.650		3.680	26.864	Sqm		
	Library	4	16.000		3.680	235.520	Sqm		
	Extra as outer Beam	10	6.000		1.300	78.000	Sqm		
						2999.155	Sqm		
	Ceiling Plaster:								
	Office	1	9.000	6.000		54.000	Sqm		
	Verandah office Side	1	16.000	3.800		60.800	Sqm		
	Photostat Room	1	3.820	3.240		12.377	Sqm		
	Class Room	4	12.500	9.000		450.000	Sqm		
	Front Verandah	1	24.000	3.600		86.400	Sqm		
						663.577	Sqm		
	Total								Rs.

02

Alchan

Project
Plot
Owners

: Proposed Repair & Renovation Law College
: CMP Degree College Campus, Prayagraj
: Principal, CMP Degree College

SN	Description of Item	No s	L (m)	B (m)	H/D (m)	Qty	Unit	Rate/ Unit	Amt (Rs. Lakhs) incl. GST
	New Plaster Work								
	Wall Plaster								
	13.12 Ch 13 13.1 (13.1.2) : 12mm Cement plaster with cement mortar in proportion of 1: 6 cement & fine sand (Dholpur sand) (Not less than in 1.25 FM) of single coat for interior plastering upto floor two level including internal rounded angles chamfers, and rounded angles not exceeding 80mm in girth and finished even and smooth.								
	Class Room	6	42.400		4.200	1068.480	Sqm		
	Room Outer	1	100.000		4.200	420.000	Sqm		
	Moot Court Wall	4	37.500		4.200	630.000	Sqm		
		4	3.500		4.200	58.800	Sqm		
	Passage (Outer Wall)	2	23.000		4.200	193.200	Sqm		
	Com Toilet	2	2.300		3.680	16.928	Sqm		
		2	2.270		3.680	16.707	Sqm		
	Staff Toilet	2	3.800		3.680	27.968	Sqm		
		2	3.000		3.680	22.080	Sqm		
	Office	2	5.800		3.680	42.688	Sqm		
		2	9.000		3.680	66.240	Sqm		
	Office Verandah	2	13.000		3.680	95.680	Sqm		
		2	3.650		3.680	26.864	Sqm		
	Library	4	16.000		3.680	235.520	Sqm		
	Extra as outer Beam	10	6.000		1.300	78.000	Sqm		
						2999.155	Sqm		
	Ceiling Plaster:								
	13.11 Ch 13 13.11 (-) : 12mm Cement plaster with cement mortar in proportion of 1:x 4 cement & fine sand (Dholpur sand) (Not less than in 1.25 FM) of single coat for interior plastering upto floor two level including internal rounded angles chamfers, and rounded angles not exceeding 80mm in girth and finished even and smooth. + 13.06 Ch 13 587 (-) : Add for extra labour to all items of plaster done in ceiling								
	Office	1	9.000	6.000		54.000	Sqm		
	Verandah office Side	1	16.000	3.800		60.800	Sqm		
	Photostat Room	1	3.820	3.240		12.377	Sqm		
	Class Room	4	12.500	9.000		450.000	Sqm		
	Front Verandah	1	24.000	3.600		86.400	Sqm		
						663.577	Sqm		
	Total							Rs.	

B2

Alcha

Project

: Proposed Repair & Renovation Law College

Plot

: CMP Degree College Campus, Prayagraj

Owners

: Principal, CMP Degree College

Sl. No.	Description of Item	No.	L (m)	B (m)	H/D (m)	Qty	Unit	Rate/Unit	Am't (Rs. Lakh) incl. GST
NEW CONSTRUCTION									
Roof Slab									
	5.11 Ch 5 284 (5.6.2) : RCC Work in slabs with 1: 1-1/2 : 3 (cement : appd Coarse Sand : 20 mm Guage stone grit) excluding supply of reinforcement and its bending but including its fixing and binding the same with 24 BWGGI Binding Wire and including the cost of Binding Wire and including necessary centering and shuttering etc and supply of all materials, labour, T & P etc required for proper completion of work including cost of Binding Wire. The rate excludes making Drip Course, which shall be paid extra. Excluding GST								
	Front Verandah	1	16.100	4.200	0.150	10.143	Cum		
	Library	1	16.000	4.200	0.150	10.080	Cum		
	Office Verandah	1	12.700	4.000	0.150	7.620	Cum		
	Office	1	6.000	3.500	0.150	3.150	Cum		
						30.993	Cum		
RCC Beam :									
	5.12 Ch 5 285 (5.6.3) : RCC Work in Light Beams with 1: 1-1/2 : 3 (cement : appd Coarse Sand : 20 mm Guage stone grit) excluding supply of reinforcement and its bending but including its fixing and binding the same with 24 BWGGI Binding Wire and including the cost of Binding Wire and including necessary centering and shuttering etc and supply of all materials, labour, T & P etc required for proper completion of work including cost of Binding Wire. The rate excludes making Drip Course, which shall be paid extra. Excluding GST								
	Beam	4	3.500	0.350	0.600	2.940	Cum		
		1	16.100	0.350	0.600	3.381	Cum		
						6.321	Cum		
Reinforcement									
	10.06 Ch 10 504 (10.3.1) : MS (tor steel or plain) in plain work such as RCC or RB Work including bending for proper shape and including supply of steel and its wastage bend, hooks and authorised overlappings shall be measured and including cost of Binding Wire. Excluding GST								
	Slab					32.282	Qtl		
	Beams					6.196	Qtl		
						38.478	Qtl		
	Total								Rs.

Project
Plot
Owners

: Proposed Repair & Renovation Law College
: CMP Degree College Campus, Prayagraj
: Principal, CMP Degree College

SN	Description of Item	No s	L (m)	B (m)	H/ D (m)	Qty	Unit	Rate/ Unit	Amt (Rs. Lakhs) incl. GST
Colour Washing / Painting									
Exteriors : Considered 25% of the total Plaster Area									
	15.10 Ch 15 660 15.11.1 : Finishing walls with water proof cement paint of approved make and quality on new work with two coats to give an even shade including supply of all materials, labour, T&P etc required for proper completion of work. + 15.11 Ch 15 661 15.11.2 : one addl. coat of Water proof Cement paint after the first two coats to give a n even shade								
	Class Room	16	21.200			4.200	1424.640	SQM	
	Verandah Wall	2	50.000			4.200	420.000	Sqm	
		2	10.000			4.200	84.000	Sqm	
	Verandah Ceiling	2	50.000			4.200	420.000	Sqm	
	Class Room Ceiling	8	13.000	9.000			936.000	Sqm	
	Exteriors	1	200.000			2.000	400.000	Sqm	
	Office	1	9.000	6.000			54.000	Sqm	
	Office side Verandah Wall	1	16.000	3.800			60.800	Sqm	
	Office Wall	2	13.000			3.630	94.380	Sqm	
	Office side Verandah Ceiling	2	16.000			3.630	116.160	Sqm	
	Library Ceiling	1	16.000	3.500			56.000	Sqm	
	Library Wall	2	20.000			3.630	145.200	Sqm	
	Office side Wall	1	16.000			3.630	58.080	Sqm	
	Moot Court Wall	2	38.000			3.630	275.880	Sqm	
	MC Ceiling	1	38.000	15.000			570.000	Sqm	
	Passage Wall	4	28.000			4.200	470.400	Sqm	
	Passage Ceiling	2	23.000	3.500			161.000	Sqm	
	Toilet, PS Room & Gallery	1	10.000	6.000			60.000	Sqm	
	Extra Wall (Parapet) of above Area	4	15.000			3.630	217.800	Sqm	
							6024.340	Sqm	
	Considered 25% for exterior painting						1506.085	Sqm	
Interiors (including Ceiling)									
	15.04 Ch 15 649 (-) : Distempering (first coat) with oil bound distemper of approved brand and manufacture and of required shade on undercoated wall surface to give an even shade over & including a priming coat with cement primer of approved brand and manufacture such as Berger, J&N, Shalimar, Asian, paints after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even with plaster of approved synthetic material and sand papered smooth including cost of all materials. + 15.05 Ch 15 651 - - for providing one addl coat over the first coat		75.00%	6024.340			4518.255	Sqm	
	Total								Rs. 0.00

B

Handwritten signature

Project
Plot
Owners

: Proposed Repair & Renovation Law College
: CMP Degree College Campus, Prayagraj
: **Principal, CMP Degree College**

SN	Description of Item	No s	L (m)	B (m)	H/ D (m)	Qty	Unit	Rate/ Unit	Amt (Rs. Lakhs) incl. GST
Summary (Estimate)									
	S.No. 2.1: Dismantling of RCC Roof Slab and Beams							Rs.	
	2.2 : Dismantling Existing Plaster Work							Rs.	
	3 : New Plaster Work							Rs.	
	4 : New Construction Roof Slab							Rs.	
	5 : Colour Washing and Painting Work							Rs.	
	Total							Rs.	
	GST @ 18%							Rs.	

Grand Total

Signature of Contractor with seal

Ayuman
Convehor, Building Committee

H. A. Chandra
Principal